

A

PUMPING STATION SURVEY



DENE-TECH SERVICES LIMITED

UNIT 10, LYMINGTON BARN, LYMINGTON BOTTOM ROAD, MEDSTEAD, Nr ALTON, HANTS GU34 5EW
Telephone/Fax: 01 420 552 509
E-mail: deneotech@globalnet.co.uk

GENERAL INFORMATION

WTW Catchment : A
Catchment Code : Unknown
Name : A SPS
Eastings : 000000 Northings: 000000
Sewer Record ID : AA12345678
Operational Control : A
Date of Survey : 12/02/2014
Surveyed by :- Company Name : Dene-Tech Services Limited
Name of Surveyor : C. Lockie

OVERFLOW DETAILS

Provided (Yes/No) : No
Type (EO/CSO) : n/a
Location : n/a

Screen (Yes/No) : n/a
Screen Type : n/a
Bar Spacing (mm) : n/a

Condition : n/a
Evidence of Pollution/Use (Yes/No) : n/a

Number of Pumps : 7 (3 DWF, 4 storm)

RISING MAIN DETAILS

Length (m) : Unknown
Diameter (mm) : DWF 450mm, storm 600mm
Material :

SURGE PROTECTION (Yes/No) No

Type :

PUMP DROP TESTS

Area of Wet Well (m ²)	122.66m ²
Test Area (m ²)	63.234m ²
Test Volume (m ³)	6.323m ³

Pump Combination	Test Start Level m(AOD)	Test Stop Level m(AOD)	Test No	Draw		Fill		Net Output
				(secs)	(l/s)	(secs)	(l/s)	(l/s)

STORM PUMP 1+2	81.703	81.603	1	54	117.09	31	203.97	321.06
	81.703	81.603	2	60	105.38	30	210.77	316.15
	81.703	81.603	3	61	103.66	30	210.77	314.43
	Average Output (l/s)							317.21

STORM PUMP 1+3	81.703	81.603	1	60	105.38	29	218.03	323.41
	81.703	81.603	2	55	114.96	29	218.03	332.99
	81.703	81.603	3	55	114.96	30	210.77	325.73
	Average Output (l/s)							327.38

STORM PUMP 1+4	81.703	81.603	1	53	119.30	31	203.97	323.27
	81.703	81.603	2	51	123.98	30	210.77	334.75
	81.703	81.603	3	52	121.60	30	210.77	332.37
	Average Output (l/s)							330.13

STORM PUMP 2+3	81.703	81.603	1	51	123.98	31	203.97	327.95
	81.703	81.603	2	48	131.73	33	191.61	323.34
	81.703	81.603	3	48	131.73	32	197.59	329.32
	Average Output (l/s)							326.87

STORM PUMP 2+4	81.703	81.603	1	52	121.60	30	210.77	332.37
	81.703	81.603	2	51	123.98	31	203.97	327.95
	81.703	81.603	3	53	119.30	31	203.97	323.27
	Average Output (l/s)							327.86

STORM PUMP 3+4	81.703	81.603	1	53	119.30	30	210.77	330.07
	81.703	81.603	2	55	114.96	30	210.77	325.73
	81.703	81.603	3	54	117.09	30	210.77	327.86
	Average Output (l/s)							327.89

PUMP DROP TESTS

Area of Wet Well (m ²)	122.66m ²
Test Area (m ²)	63.234m ²
Test Volume (m ³)	6.324m ³

Pump Combination	Test Start Level m(AOD)	Test Stop Level m(AOD)	Test No	Draw		Fill		Net Output
				(secs)	(l/s)	(secs)	(l/s)	(l/s)

STORM PUMP 1+2+3	81.703	81.603	1	50	126.48	26	243.23	369.71
	81.703	81.603	2	50	126.48	28	225.86	352.34
	81.703	81.603	3	50	126.48	26	243.23	369.71
Average Output (l/s)								363.92

STORM PUMP 1+2+4	81.703	81.603	1	50	126.48	29	218.07	344.55
	81.703	81.603	2	48	131.75	26	243.23	374.98
	81.703	81.603	3	51	124.00	29	218.07	342.07
Average Output (l/s)								353.87

STORM PUMP1+3+4	81.703	81.603	1	53	119.32	29	218.07	337.39
	81.703	81.603	2	51	124.00	27	234.22	358.22
	81.703	81.603	3	51	124.00	26	243.23	367.23
Average Output (l/s)								354.28

STORM PUMP 2+3+4	81.703	81.603	1	53	119.32	27	234.22	353.54
	81.703	81.603	2	53	119.32	27	234.22	353.54
	81.703	81.603	3	53	119.32	28	225.86	345.18
Average Output (l/s)								350.75

DWF PUMP 2 FLOW METER			1					
			2					
			3					
Average Output (l/s)								106.00

			1					
			2					
			3					
Average Output (l/s)								0.00

LEVEL DETAILS

(including Pipework and Electrodes/Floats)

TBM Levels

No	Position	Level (m AOD)
1	SP48757402	86.488
2	DWF wet well	87.033
3	Storm wet well	87.030
4		
5		

Wet Well Dimensions (m)	12.50m ϕ
Wet Well Area (m ²)	122.66m ² (not test area)
Wet Well Cover Level (m AOD)	87.033m

Pipework (Invert Levels)

No	Position	TBM Level	Depth to IL	Level (m AOD)
1	Pipe A 900mm	87.033m	8.65m	78.383
2	Pipe B 600mm	87.033m	8.65m	78.383
3	Weir wall	87.033m	5.33m	81.703
4	Sump	87.033m	8.90m	78.133
5	Pumps	87.033m	8.60m	78.433
6	Benching	87.033m	7.65m	79.383
7				

Electrodes/Floats

No	Position	TBM Level	Depth to IL	Level (m AOD)
1	DWF duty start	87.033m	8.06m	78.973
2	DWF assist start	87.033m	7.96m	79.073
3	DWF stand-by start	87.033m	-	-
4	DWF duty stop	87.033m	8.26m	78.773
5	DWF assist stop	87.033m	8.25m	78.783
6	Duty storm start	87.030m	5.73m	81.300
7	1 st assist storm start	87.030m	5.53m	81.500
8	2 nd assist storm start	87.030m	4.72m	82.310
9	Stand-by storm start	87.030m	-	-
10	Duty storm stop	87.030m	7.38m	79.650
11	1 st assist storm stop	87.030m	6.88m	80.150
12	2 nd assist storm stop	87.030m	5.02m	82.010
13	High level alarm	87.033m	5.00m	82.033

PUMPING STATION GENERAL DATA

MOTOR DETAILS

No	Type	Make	Model	Serial No	Plated Capacity	Remarks
1						
2						
3						
4						

PUMP DETAILS

No	Type	Make	Model	Serial No	Plated Capacity	Operation
1	3171.091	FLYGT	-	0840013	1460rpm	Auto rotation
2	3171.091	FLYGT	-	0840014	1460rpm	Auto rotation
3	3171.091	FLYGT	-	0840015	1460rpm	Auto rotation
4	3202.090	FLYGT	-	-	970rpm	Auto rotation
5	3202.090	FLYGT	-	-	970rpm	Auto rotation
6	3202.090	FLYGT	-	-	970rpm	Auto rotation
7	3202.090	FLYGT	-	-	970rpm	Auto rotation

ARRANGEMENT OF TELEMETRY

Mains Failure (Yes/No)	Yes
High Water Level in Wet Well (Yes/No)	Yes
High Water Level in Dry Well (Yes/No)	n/a
Motor Overload (Yes/No)	No

Other Telemetry (Details)

1	Pumps failed
2	Dosing failed
3	
4	

GENERATOR DETAILS

Generator Socket provided (Yes/No)	Yes
Permanent Generator installed (Yes/No)	No
Size of Generator (kVA)	
Generator Make	
Generator Model	
Fuel Type	
Type of Supply (Phase)	
Auto Start (Yes/No)	

SITE DETAILS

1	Location of Station (Area Details)	Paynes Lane industrial estate
2	Access to Station (Road Details)	Made road
3	Surroundings (Urban/Rural/Residential/ Commercial/Industrial)	Industrial
4	Distance from station to nearest inhabited buildings (m)	100m+
5	Access for Vehicle (Van/Tanker/None)	Tanker
6	Turning for Vehicle (Van/Tanker/None)	Van
7	Access Difficulties (Details)	None
8	Fencing (Chain Link/Timber/Other/None)	Chain link
9	Gates (Steel/Timber/Other/None)	Steel
10	Non-operational Areas (Grass/Shingle/Other/None)	Shingle

STRUCTURES

1	Superstructure Type (Brick/Industrial/Other)	Brick
2	Roof (Pitched/Flat/Tiles/Slates/Sheets)	Flat
3	Substructure (Wet Well/Dry Well/Submersible)	Wet well
4	Access to Dry Well (Yes/No/Details)	n/a
5	Access to Wet Well (Yes/No/Details)	Ladder
6	Construction (Brick/Pre Cast Concrete/Insitu Concrete)	Pre cast concrete
7	Wet Well Ventilation (Forced/Vent Pipe/None)	None
8	Dry Well Ventilation (Forced/Vent Pipe/None)	n/a
9	Emergency Condition Report (Signs of Serious Defects - Details)	None
10	General Comments	DWF pump Nos.1 and 3 are not working. DWF pump No.2 is not beating incoming flow. Individual storm pumps are not beating flow. DWF pump duty auto rotate every 5 hours and storm pump duty rotates every 4 hours. DWF pump No.2 rate was taken from flow meter reading. Unable to close incoming rotork valves for DWF pump tests. Stand-by pumps start if duty/assist pumps fail.